



**Interconnection Feasibility Study Report
GIP-149-FEAS-R0**

**Generator Interconnection Request #149
70 MW Wind Generating Facility
Cumberland (L-6535), NS**

May 28, 2008

Control Centre Operations
Nova Scotia Power Inc.

Executive Summary

A feasibility study was conducted in response to Interconnection Request number 149 (IR149) which proposes to connect 70 MW of wind powered generation in Cumberland Co., Nova Scotia. The customer has requested ERIS service. This facility would connect to the transmission system at a location adjacent to the New Brunswick border on 138 kV line L-6535. Alternatively the facility may be connected to L-6536.

Both the L6535 and L6536 interconnections appear feasible. The direct interconnection costs are estimated to be \$6.1 million with a 12-24 month time to construct. The L6535 interconnection has a higher potential of causing post contingency overloads for contingencies in the northern Nova Scotia area. Thus the L6536 interconnection is preferred.

Generating facilities added to the system in northern Nova Scotia (between Truro and New Brunswick) can have an impact on the transfer capability between Nova Scotia and New Brunswick and the special protection systems (SPS) that have been installed to facilitate those transfers. This project will necessitate upgrading these SPSs but allocation of those costs are dependent on whether projects that are ahead of this project in the Generation Interconnection Queue (Queue) proceed. These costs are identified as indirect or to be determined (TBD) in section 10. A discussion regarding these transfer capabilities and the SPSs is included in section 8.

Table of Contents

| | Page |
|---------------------------------------------------------------------|------|
| Executive Summary | ii |
| 1 Introduction | 1 |
| 2 Scope | 1 |
| 3 Assumptions | 2 |
| 4 Projects with Higher Queue Positions | 2 |
| 5 Short-Circuit Duties | 3 |
| 6 Thermal Limits..... | 4 |
| 7 Voltage Control | 5 |
| 8 System Limitations (Transfer Capability)..... | 6 |
| 9 Expected Facilities Required for Interconnection | 8 |
| 10 Magnitude of NSPI Interconnection Facilities Cost Estimate | 11 |
| 11 Preliminary Scope of SIS..... | 12 |

1 Introduction

The Interconnection Customer (IC) submitted an Interconnection Request to NSPI for a proposed 70 MW wind generation facility interconnected to the NSPI system via 138 kV line L-6535 that runs between the 30N-Maccan and 410N-Memramcook substations. The 138 kV line L6536 was identified as an alternative Point of Interconnection (POI). The IC signed a Feasibility Study Agreement to study the connection of their proposed generation to the NSPI transmission system. This report is the result of that Study Agreement. The generation site would be located adjacent to the Nova Scotia – New Brunswick border and in between lines L-6535 and L-6536, and connect to line L-6535 or alternatively L-6536.

2 Scope

The Interconnection Feasibility Study (FEAS) report shall provide the following information:

- i. preliminary identification of any circuit breaker short circuit capability limits exceeded as a result of the interconnection;
- ii. preliminary identification of any thermal overload or voltage limit violations resulting from the interconnection; and
- iii. preliminary description and non-binding estimated cost of facilities required to interconnect the Generating Facility to the Transmission System, the time to construct such facilities, and to address the identified short circuit and power flow issues.

The scope of this FEAS includes modeling the power system in normal state (with all transmission elements in service) under anticipated load and generation dispatch conditions.

For Energy Resources Integration Service (ERIS), if the FEAS determines that transmission upgrades are required as a result of thermal overload, voltage violation, or equipment rating, then the FEAS will determine the amount of generation that can be installed without necessitating major transmission upgrades. The FEAS will provide a preliminary high level cost estimate of the direct interconnection costs.

For NRIS service type, the FEAS will identify any transmission upgrades required as the result of thermal overload, voltage violation, or equipment rating. The FEAS will attempt to provide high level cost estimates for such upgrades and the direct interconnection costs.

A more detailed analysis of the technical implications of this development will be included in the System Impact Study (SIS) report. This may include system stability analysis, single or double contingencies, off-nominal frequency operation, off-nominal voltage operation, low voltage ride through, harmonic current distortion, harmonic voltage distortion, system protection, special protection system (SPS), automatic generation control (AGC) and islanded operation. The impacts on neighbouring power systems and the requirements set by reliability authorities such as Northeast Power Coordinating Council (NPCC), North American Reliability Council (NERC), and Nova Scotia Power (NSPI) will be addressed at that time. The SIS may identify additional costs and upgrades that were not identified in this FEAS.

As well, a separate facility study will follow the SIS in order to ascertain the final cost estimate for the transmission upgrades requirement.

3 Assumptions

The POI and configuration studied is as follows:

- i. 70 MW wind farm comprised of 47 – 1.5 MW GE 1.5 SLE wind turbines and with ERIS service requested.
- ii. The wind generating facility will interconnect to L-6535 at a location adjacent to the New Brunswick border. An alternative POI is L-6536
- iii. Transformer Impedance assumed at 7% (on ONAN Base), rated 47/63/78 MVA.
- iv. This feasibility study is based on the assumption that projects that are ahead of this project in the Generation Interconnection Queue (Queue) will not proceed but impacts are reviewed qualitatively.

4 Projects with Higher Queue Positions

As of 17 December 2007 the following projects can proceed ahead of this project, due to their position in the Queue, and have the status indicated.

In-service and committed generation projects

Wind Generation – 30.5 MW - connected to L-5027 (in-service)

Wind Generation – 15 MW – connected to L-5573 (in-service)

Generation projects with a higher Queue position, not yet committed

IR008 Wind – Guysborough (L-5527B) 15 MW NRIS – FAC complete

IR017 Wind – Lunenburg (L-6004) 100 MW NRIS- FEAS complete

IR023 Wind – Inverness (L-6549) 100 MW NRIS - FEAS complete

IR042 Wind – Cape Breton (VJ) 100 MW NRIS- FEAS complete

IR045 Wind – Cumberland (L-6535) 35 MW NRIS- SIS complete

IR046 Wind – Colchester (L-6513) 32 MW ERIS- FEAS complete

IR056 Wind – Cumberland (L-5058) 34 MW ERIS- FEAS complete

IR067 Wind – Annapolis (L-5026) 40 MW ERIS- FEAS complete

IR068 Wind – Digby (L-6513) 35 MW ERIS- FEAS complete

IR082 Wind – Colchester (L-5040) 45 MW ERIS- FEAS complete

IR084 Wind – Pictou (L-7004) 50 MW ERIS- FEAS complete

IR086 Wind – Pictou (L-7003) 50 MW NRIS- FEAS complete

IR114 Wind – Pictou (L-6511) 60 MW NRIS- FEAS complete

IR115 Wind – Pictou (L-7003) 120 MW NRIS- FEAS complete

IR117 Wind – Shelburne (L-5027) 10 MW ERIS- FEAS complete

IR126 Wind – Cumberland (L-6513) 70 MW ERIS- FEAS complete

IR128 Wind – Cumberland (L-6535) 40.5 MW ERIS- FEAS complete

IR130 Wind – Cape Breton (L-7012) 200 MW NRIS- FEAS complete

IR131 Wind – Cape Breton (L-5580) 11.5 MW ERIS- FEAS complete

IR137 Wind – Richmond (1C) 10 MW NRIS- FEAS complete

IR140 Wind – Antigonish (L-7004) 30 MW NRIS- FEAS complete

IR141 Wind – Digby (77V) 30 MW NRIS- FEAS complete

This project and projects IR045, 046, 056, 126 and 128 add generation to transmission facilities that are part of the Nova Scotia to New Brunswick interconnection. These projects will compete for 138 kV transmission capacity. The remaining projects may have an impact on this project in that all projects will require use of transmission facilities to deliver power to the load centers.

The SIS will be based on the assumption that all projects that are ahead of this project in the Queue are in-service. Should any project that is ahead of this project be withdrawn, or changed, within the established procedures then the SIS for this project must be updated accordingly, at the project proponents expense.

5 Short-Circuit Duties

The maximum (future) expected short-circuit levels are 5000MVA on 138 kV systems.

The short-circuit levels in the area before and after this development are provided in Table 5-1 below.

| Table 5-1: Short-Circuit Levels. Three-phase MVA (1) | | |
|------------------------------------------------------|-------------------------------------|-----------------------------------------|
| Location | This generating facility in service | This generating facility not in service |
| All transmission facilities in service | | |
| 30N- Maccan – 138 kV | 1180 | 1070 |
| L-6535 Tap – 138 kV(2) | 1350 | 1140 |
| L-6535A (30N-Maccan to POI) Out | | |
| 30N- Maccan – 138 kV | 670 | 670 |
| L-6535 Tap – 138 kV(2) | 1060 | 860 |
| L-6535B (410N-Memramcook to POI) Out | | |
| 30N- Maccan – 138 kV | 860 | 660 |
| L-6535 Tap – 138 kV(2) | 720 | 510 |

- (1) Classical fault study
(2) POI L6535

In determining the maximum short-circuit levels with this generating facility in service the generators have been modeled as conventional machines with reactance comparable to induction machines regardless of the type of generators proposed. This provides a worst case estimation.

The increase in short-circuit levels due to IR #149 are not significant.

6 Thermal Limits

Line L-6535 is currently rated 143/143 MVA (summer/winter). The ratings of L-6535 are limited by the capabilities of a switch and metering at the 30N-Maccan terminal. Thus the ratings can be easily raised. Line L-6536 is currently rated 110/165 MVA (summer/winter). The ratings of L-6536 are limited by conductor to ground clearance. The addition of this facility alone will not result in any

thermal overloads for single contingencies starting with all transmission elements in service.

The requirement for restrictions or curtailments of this facility when operating with an element (transmission line, transformer, bus etc) out of service (N-1 operation) will be further assessed in the SIS.

This generating facility will require a curtailment scheme and high speed rejection scheme for integration with NSPI SCADA controls and SPSs to maximize the capability of NSPIs transmission system, system security, and production of all generating facilities.

It was noted in this assessment that if all queued projects proceed then there is potential for overloading facilities in northern Nova Scotia for contingencies in that area. This may be remedied by developing a northern Nova Scotia SPS scheme. It was also noted that the potential for overloads and requirement for post contingency SPS action will be less if the POI is L6536. Therefore if all other costs and impacts appear equal, L6536 would be the preferred POI. This analysis does not include the impact of any new generation may be constructed in New Brunswick

7 Voltage Control

The ratio of short-circuit level to generating capacity, with a 138 kV interconnection, under system normal conditions is 16 (1140/70) and is 7.2 (510/70) with one line out of service. There should therefore be no specific issues regarding voltage control and power quality due to the addition of this facility alone.

The facilities included with this installation must be such that the facility is capable of providing both lagging and leading power factor of 0.95, measured at the high voltage (transmission) IC substation, when the facility is delivering full power. A centralized controller will be required which adjusts individual generator real and reactive power output, in real time, and regulate the voltage at the high-voltage terminals of the IC substation. The voltage controls must be responsive to voltage deviations at the high voltage terminals of the IC substation, be equipped with a voltage set-point control, and also have facilities that will slowly adjust the set-point over several minutes (5-10) to maintain reactive power just within the individual generators capabilities. The latter control may be referred to as a slow-Q control. Details of the specific control features, control strategy and settings will be reviewed and addressed in the SIS.

NSPI must have manual and remote control of the voltage set-point, the slow-Q controls and reactive power output from this facility.

This facility must also have low-voltage ride-through capability as per FERC order 661A. The SIS will state any additional specific options, controls and additional facilities that are required to achieve this.

8 System Limitations (Transfer Capability)

The existing Nova Scotia import capability, measured at the Nova Scotia – New Brunswick border, is limited to the lesser of 300 MW or 22% of load. This is the maximum import that can be scheduled across the Nova Scotia – New Brunswick interface with all facilities in service. In addition, when Nova Scotia is importing 300 MW the loss of the largest NSPI generating contingency (two units) will increase the import level an additional 328 MW to 628 MW. The Nova Scotia Power System operator will then return the import level to 300 MW as quickly as possible and within 30 minutes of the generation loss. This is achieved by loading generation reserves and, if necessary, shedding non-firm load. Thus the system must be capable of operating with a Nova Scotia import of 300 MW and the subsequent loss of 328MW of generation and with acceptable voltages and all facilities within their thermal capabilities. As generation is added in northern Nova Scotia transmission reinforcement will be required in order to maintain this transmission capability. L-6513 is the limiting transmission facility with a summer thermal rating of 110 MVA. When the generation installed in northern Nova Scotia exceeds 60 to 90 MW (depending on location) upgrading of L-6513 will be required or a second 138 kV line be required. Alternatively the two-unit contingency can be removed by adding a circuit breaker at 50N-Trenton and reconfiguring the 88S-Lingan bus. If projects that are ahead of this project in the Queue proceed, then this project may cause overloading of L-6513, following this contingency, thereby necessitating upgrades to line L-6513.

The existing Nova Scotia export capability, measured at the Nova Scotia – New Brunswick border, is 300 MW but can be increased to 350 MW under certain operating conditions. NSPI has a commitment to hold portion of the total export capability in reserve, on a long term basis, as part of its reserve sharing agreement with the New Brunswick System Operator (NBSO). With all facilities in service and a 350 MW export, all facilities must be loaded within their thermal capabilities and with acceptable system voltages.

NSPI has made extensive use of Special Protection Systems (SPS) in order to reduce/avoid capital expenditures and improve overall cost efficiencies. These systems act to maintain system stability and remove equipment overloads, post contingency, by rejecting generation and/or shedding load. NSPI continues to have no objection to the application of such systems to reduce interconnection costs. However, these systems must be designed, installed and periodically tested in accordance with criteria, guidelines and procedures that are set forth by

reliability organizations which include NSPI, NPCC and NERC. The application, design, maintenance and testing of SPSs must comply with all present and future requirements. The NSPI system has several congested interfaces (transmission corridors that are regularly operated at limits). NSPI has made use of SPS to increase transfer limits on these interfaces. There are practical limits to the amount of generation and load that can be rejected by SPSs and the amount of generation that can be curtailed following a single contingency loss before system stability and reliability are compromised.

There are a number of SPSs and protective systems employed by NSPI and the NBSO to permit these high transfer levels between the two systems. NSPI has an “Import Power Monitor” that acts to separate the two systems following the loss of the 345 kV tie (L-8001/L-3025), by cross-tripping L-6513. Currently this system is armed when imports exceed 100MW. Once this SPS operates, the load and generation in northern Nova Scotia are disconnected from the Nova Scotia system (but remain connected to New Brunswick). The Nova Scotia system is then islanded and relies on under frequency load shedding (UFLS) schemes to shed load across Nova Scotia to make up the generation deficiency and restore balance. As generation is located in northern Nova Scotia, unless changes are made to this SPS, the scheme will be compromised (as will the Nova Scotia import capability) as it will disconnect generation resources (in northern NS) from the NSPI system. When generation in this area exceeds 40 MW, this SPS will as a minimum, have to be modified by relocating the system separation point from L-6513 at Onslow to the NB border (Maccan and Memramcook). When the generation in northern Nova Scotia exceeds 125 MW then either L-6513 must be thermally upgraded or an additional 138 kV line constructed. Stability and ride-through capability of generation in this area will be critical. This import SPS can also be triggered by a number of SPSs in New Brunswick for contingencies near Memramcook and Salisbury.

When NSPI is exporting power such that the loss of L-8001/L-3025 will result in thermally overloading L-6513 (NS export approximately 100 MW) the “NS Export Power Monitor” is armed. Should L-8001 trip, then this SPS will reject generation in eastern Nova Scotia to ensure that L-6513 is not thermally overloaded and does not trip. We do not expect this project, in addition to projects that precede it in the Queue, to compromise this SPS.

There are a number of proposed generation additions in New Brunswick that may have an impact on projects in northern NS and visa versa. Their POI, size and relative position of the NS and NB interconnection Queues will determine the impact. This will be resolved through collaboration with NBSO at the SIS stage.

As the penetration of wind generation increases in this area it is expected that the reliance on the existing SPS scheme may compromise system security. This will depend on the amount of wind generation and its variability. At some level we

expect either this SPS scheme will be redesigned or transmission expansions required for system security. The transmission expansions, if required, may include a second 138 kV transmission line between 1N-Onslow and 74N-Springhill. This requirement will be determined by the SIS.

This generating facility will also increase loading on the Onslow South corridor (Truro to Halifax) by replacing generation south and west of Truro. This may require increased reactive support requirements in the Halifax area or invoke facility additions that can reduce the reactive support requirements. This will be evaluated in the SIS.

The SIS will determine the facility changes that are required to permit higher transmission loadings while maintaining compliance with NERC/NPCC standards and in keeping with good utility practices.

9 Expected Facilities Required for Interconnection

We expect that based on the above discussions that this project is feasible at the requested capacity, subject to the SIS. The interconnection facilities required are as follows:

a) 138 kV Interconnection L-6535

Additions/Changes to NSPI systems

- i. POI Substation. Install a 138 kV three circuit breaker ring bus at the POI on L-6535 with protection and telemetry
- ii. Control and Communications between 30N-Maccan/NSPI and the IC substation
- iii. Inclusion of generating facility into NSPIs generation rejection SPSs and load curtailment schemes
- iv. Relocation of NS-NB interprovincial revenue-class metering from 30N-Maccan to the POI Substation.
- v. Relocation of separation point for the “NS Import Power Monitor” from the 1N-Onslow terminal of L-6513 to the IC substation and the Memramcook terminal of L-6536.
- vi. Install circuit breaker at 50N-Trenton and reconfigure the 88S-Lingan bus. This may not be required depending on the status of preceding projects in the Queue
- vii. Rebuild L6513 between the interconnection substation of projects IR128 and IR046 and 1N-Onslow. This or upgrading may or not be required depending on the status of preceding projects in the Queue

- viii. Development of SPS scheme for northern Nova Scotia contingencies that rejects generating facilities in that area to relieve post contingency overloads. This may or may not be required depending on whether or not higher queued projects proceed.

Additions/Changes to be included at the IC's Interconnection Facilities:

- ix. 138 kV IC Substation. This will include protections as acceptable to NSPI, An RTU to interface with NSPIs SCADA with telemetry and controls as required by NSPI. NSPI will require real-time monitoring of the IC and POI substations.
- x. Facilities to provide 0.95 leading and lagging power factor when delivering rated output at the 138kV IC Substation POI when the voltage at that point is operating between 95 and 105 % of nominal.
- xi. Centralized controls. These will provide centralized voltage set-point controls and slow-Q controls which acts to control the voltage on the 138 kV system and the reactive output of the machines. Responsive (fast-acting) controls are required. The controls will also include a curtailment scheme which will limit or reduce total output from the facility, upon receipt of a telemetered signal from NSPIs SCADA system. The controller will also limit the load ramp rate of the facility to within limits set by NSPI and/or telemetered from NSPIs SCADA system.
- xii. NSPI to have control and monitoring of reactive output of this facility, via the centralized controller. This will permit the NSPI operator to raise or lower the voltage set-point and change the status of any slow-Q controls, remotely. NSPI will also have remote manual control of the load curtailment scheme.
- xiii. Low voltage ride-through capability in accordance with FERC Order 661A post-transitional requirements
- xiv. Facilities for NSPI to execute high speed rejection of generation (transfer trip)
- xv. Accessible and tree-cleared lands or Rights Of Way (ROW) acceptable to NSPI for design and construction of any required new transmission line or Transmission Provider's substation.

b) 138 kV Interconnection L-6536

Additions/Changes to NSPI systems

- i. POI Substation. Install a 3X138 kV circuit breaker ring bus at the POI on L-6536 with protection and telemetry

- ii. Control and Communications between 74N-Springhill/NSPI and the IC substation
- iii. Inclusion of generating facility into NSPIs generation rejection SPSs and load curtailment schemes
- iv. Relocation of separation point for the “NS Import Power Monitor” from the 1N-Onslow terminal of L-6513 to the 30N-Maccan terminal of L-6535 and the Memramcook terminal of L-6536. Should IR045 proceed then the SPS would be moved to that POI substation rather than Maccan.
- v. Install circuit breaker at 50N-Trenton and reconfigure the 88S-Lingan bus. This may not be required depending on the status of preceding projects in the Queue
- vi. Rebuild L6513 between the interconnection substation of projects IR128 and IR046 and 1N-Onslow. This or upgrading may or not be required depending on the status of preceding projects in the Queue
- vii. Development of SPS scheme for northern Nova Scotia contingencies that rejects generating facilities in that area to relieve post contingency overloads. This may or may not be required depending on whether or not higher queued projects proceed

Additions/Changes to be included at the IC’s Interconnection Facilities:

- viii. 138 kV IC Substation. This will include protections as acceptable to NSPI, An RTU to interface with NSPIs SCADA with telemetry and controls as required by NSPI. NSPI will require real-time monitoring of the IC and POI substations.
- ix. Facilities to provide 0.95 leading and lagging power factor when delivering rated output at the 138kV IC Substation POI when the voltage at that point is operating between 95 and 105 % of nominal.
- x. Centralized controls. These will provide centralized voltage set-point controls and slow-Q controls which acts to control the voltage on the 138 kV system and the reactive output of the machines. Responsive (fast-acting) controls are required. The controls will also include a curtailment scheme which will limit or reduce total output from the facility, upon receipt of a telemetered signal from NSPIs SCADA system. The controller will also limit the load ramp rate of the facility to within limits set by NSPI and/or telemetered from NSPIs SCADA system.
- xi. NSPI to have control and monitoring of reactive output of this facility, via the centralized controller. This will permit the NSPI operator to raise or lower the voltage set-point and change the status of any slow-Q controls, remotely. NSPI will also have remote manual control of the load curtailment scheme.

- xii. Low voltage ride-through capability
- xiii. Facilities for NSPI to execute high speed rejection of generation (transfer trip)
- xiv. Accessible and tree-cleared lands or Rights Of Way (ROW) acceptable to NSPI for design and construction of any required new transmission line or Transmission Provider's substation.

10 Magnitude of NSPI Interconnection Facilities Cost Estimate

a) 138 kV Interconnection L-6535

| Determined Cost Items | Estimate |
|-----------------------------------------------------------|-----------------|
| i) NSPI POI Substation. Install 3X138 kV breaker ring bus | \$3,600,000 |
| ii) Site Development | 1,000,000 |
| iii) Control & Communications between NSPI and customer | 500,000 |
| iv) Additions and changes to NSPI SPSs (NSPI costs only) | 100,000 |
| v) Protection changes 30N-Maccan and Memramcook | 100,000 |
| vi) Relocate NSPI Import Power SPS cross-trip | 200,000 |
| vii) Contingency (10%) | 550,000 |

Total of Determined Cost Item **\$6,050,000**

| To Be Determined Cost Items | <u>TBD (SIS)</u> |
|-----------------------------------------------------------------|-------------------------|
| i) Rebuild L-6513 from IR126 POI to 1N-Onslow | 9,000,000 |
| ii) Circuit breaker 50N-Trenton, reconfigure 88S-Lingan | 2,500,000 |
| iii) Develop northern NS SPS scheme | 300,000 |
| iv) System additions required for system stability and security | TBD |
| v) Unforeseen impacts in NB system | TBD |
| Total: | TBD |

The above estimate includes the additions/changes to NSPI system only. The cost of the IC substation facilities on the IC side of the point of change of ownership are not included. Items identified, to be determined (TBD), will be assessed by the SIS.

NSPI estimates the time required to construct the above facilities at 12-24 months provided that no more than 2 to 3 projects per year go forward, and assuming all easements and permits are provided and complete.

b) 138 kV Interconnection L-6536

| Determined Cost Items | Estimate |
|----------------------------------------------------------|-----------------|
| i) NSPIPOI Substation. Install 3X138 kV circuit ring bus | \$3,600,000 |
| ii) Site Development | 1,000,000 |
| iii) Control & Communications between NSPI and customer | 500,000 |
| iv) Additions and changes to NSPI SPSs (NSPI costs only) | 100,000 |
| v) Protection changes 74N-Sprinhill and Memramcook | 100,000 |
| vi) Relocate NSPI Import Power SPS cross-trip | 200,000 |
| vii) Contingency (10%) | 550,000 |

Total of Determined Cost Item **\$6,050,000**

| To Be Determined Cost Items | <u>TBD (SIS)</u> |
|-----------------------------------------------------------------|-------------------------|
| i) Rebuild L-6513 from IR126 POI to 1N-Onslow | 8,000,000 |
| ii) Circuit breaker 50N-Trenton, reconfigure 88S-Lingan | 2,500,000 |
| iii) Develop northern NS SPS scheme | 300,000 |
| iv) System additions required for system stability and security | TBD |
| v) Unforeseen impacts in NB system | TBD |
| Total: | TBD |

The above estimate includes the additions/changes to NSPI system only. The cost of the IC substation facilities on the IC side of the point-of-change-of-ownership are not included. Items identified, to be determined (TBD), will be assessed by the SIS.

NSPI estimates the time required to construct the above facilities at 12-24 months provided that no more than 2 to 3 projects per year go forward, and assuming all easements and permits are provided and complete.

11 Preliminary Scope of SIS

The following provides a preliminary scope of work for the subsequent SIS. It will be finalized following collaboration with NBSO. This is a generic scope applicable to all generation Interconnection Requests in this northern area.

The SIS will include a more comprehensive assessment of the technical issues and requirements to interconnect generation as requested. In addition this will include contingency analysis, system stability and ride through capability and operation following a contingency (N-1 operation). The SIS must determine the facilities required to operate this facility at full capacity, withstand any first contingencies (as defined by NPCC/NERC) and identify any restrictions that must be placed on the system following a first contingency loss.

The SIS will confirm the options and ancillary equipment that the customer must install to control flicker, voltage and ensure that the facility has the required ride-through capability.

The study will identify any additional required changes to SPSs and any additional facilities required to maintain the import/export capabilities. It will include the impacts of generation that precedes this project in the NS and NB Queues. The SIS will also identify any generation that must be rejected by SPSs (new or existing) to ensure acceptable post contingency voltages, equipment loadings and system stability. The SIS will also identify any generation whose operation will be curtailed with any single element out of service.

The following outline provides the minimum scope that must be completed in order to assess the impacts. It is recognized that the actual scope may deviate, to achieve the primary objectives.

The SIS will determine the following

- Facilities that the customer must install to meet the requirements of the GIP
- The minimum transmission additions/upgrades that are necessary to permit operation of this generating facility, under all dispatch conditions, catering to the 1st contingencies listed.
- Impact on the operation of existing NS import/export and Langan over-frequency SPS in terms of arming levels, arming means and operating limits.
- Impact on NB SPSs in southeast corridor
- Conceptual specification of any additional (proposed) SPSs
- Impact of generation addition on UFLS adequacy (forced islanding schemes)
- Impact of generation variability on SPS operation and forced islanding scheme
- Impact of generation variability on islanded operation
- Guidelines and restrictions applicable to N-1 operation (curtailments etc)
- In addition to the SPSs the UVLS systems in NB must be included in these assessments

The SIS will be based on the following bases cases

| Power flow base cases | Variations | |
|-----------------------|--------------------|----------------------|
| Winter Peak | import 200 MW | export 200MW |
| Fall Peak | import 100,200,300 | export 100, 200, 300 |
| Summer Peak | import 100,200,300 | export 100, 200, 300 |
| Summer Light Load | import 100,200 | export 100, 250, 350 |

*Summer Peak export will have high NB-NE flows

*Winter peak import case will have high NE-NB flows

In each case accommodations for the addition of wind generation will be made to the dispatch by changing the unit commitment, for that day, ensuring that sufficient capacity is available to meet the daily peak load. The assumptions regulating regulation, load following and unit commitment at the minimum daily load (two shifting etc) will be noted.

To complete this assessment the following 1st contingencies, as a minimum, will be assessed

- L-8001/L-3025
- L-3006 – with and without NBPT SPS operation
- Memramcook 345/138 kV transformer
- L-6513
- L-6514
- L-6535/L-1159
- L-6536/L-1160
- L-8003
- L-8002 & L-8003 (common circuit breaker)
- L-8003 & L-8004 (common circuit breaker)
- L-8001 & 67N-T81 TX (common circuit breaker)
- L-3006 & L-3025 & Memramcook 345/138 kV Tx (common breaker)
- L-3006 & L-3017 (common breaker)
- 1N-B61
- L-1108/1190 Common 138kV structure
- Loss of 180 MW of load under peak load conditions and 250 MW under light load conditions
- Loss of largest generation – Pt. Aconi 174MW net
- Loss of two generating units at Lingan – 312 Net
- Loss of the Trenton Bus (Two units with load)

To complete this assessment the dynamics of the following 1st contingencies, as a minimum, will be assessed

- 3 phase fault L-8001/3025 at 67N-Onslow, NS Import SPS operation (islanding)
- 3 phase fault L-3006 at Memramcook, NB SPS/UVLS operation (islanding)
- 3 phase fault L-3006 at Salisbury, NB SPS/UVLS operation (islanding)
- 3 phase fault L-8003 at 67N-Onslow
- 3 phase fault L-8002 at 67N-Onslow
- Slg L-3017, drops L-3017&L-3006 (common CB), NB SPS/UVLS operation,
- Slg Memramcook T3, drops L-3006 (common CB), NB SPS/UVLS operation
- Slg L-8002 at Onslow, drops L-8003, Grp5 SPS Operation
- 3 phase fault at (9N-Hopewell, drops L-8003,8004, bus, SPS operation
- 3 phase fault 1N-Onslow 138 kV bus B61
- 3 phase fault 74N-Springhill 138 kV bus

After determining the changes/additions that are required to facilitate this interconnection “N-1” operation will be assessed. The objective is to determine the operating restrictions or curtailments that must be enforced to ensure secure operation of the system. This provides a final test to ensure that the facilities are adequate and the customers business risks conveyed.

- Contingency analysis, as required
- Dynamics simulation, as required
- Determination of total generation constrained

The “N-1” assessment will include, but not be limited to, the following. The “N-1” assessment will determine the operational constraints that must be applied for “N-1” operation after the facility upgrades/additions that are recommended, for the interconnection, are constructed.