



Facilities Study Infrastructure Report

Generator Interconnection Request #227

Establishing a 23 kV System Interconnection
For a 10.2 MW Biomass Generation Source

Hantsport, Nova Scotia

Prepared by: Garry Theriault, P.Eng.
Garry Theriault, P.Eng.
Consultant, Southgate Engineering Services

Date: 2011-10-11

Approved by: Tim Leopold
Tim Leopold, P.Eng.
Director, Project Implementation

Date: 2011-10-14

Facilities Study Report

System	Description
<p>1.0</p> <p>2.0</p> <p>2.1</p>	<p>INTRODUCTION</p> <p>This project provides for the establishment of a 23 kV system connection for a new 10.2 MW biomass powered generating facility located between the Nova Scotia Power Inc (NSPI) 20V-Five Points and 41V [REDACTED] substations. See Appendix A Project Site Location Drawings for details.</p> <p>The Point of Interconnection shall be on the existing 23kV line (L-4048), within 50 m from the 41V [REDACTED] substation. See Appendix C One Line Diagram of Point of Interconnection for details.</p> <p>The cost estimates provided are good faith, best estimates, based on Section 3.0 Scope of Work defined in this Facilities Study Report. The assumed contingency for this project is 10%. The Customer [REDACTED] will be responsible to pay NSPI actual incurred costs associated with this project; be it higher or lower than the estimate provided.</p> <p>This Interconnection Facilities Study Report is based on the Revised Standard Generator Interconnection Procedures as approved by the UARB on February 10, 2010 and the System Impact Study Report GIP-IR227-SIS-R0 issued by Ms. Joy Brake P.Eng. of NSPI on January 11, 2011.</p> <p>SUMMARY</p> <p>Estimated Costs</p> <p>The estimated cost for NSPI to provide a 23 kV Interconnection to the [REDACTED] biomass powered generating facility is \$657,206 (HST excluded), of which approximately \$499,000 would be considered network upgrade costs. This cost estimate is summarized below in Table 1: [REDACTED] Interconnection Biomass Generating Facilities Estimate (Overall Costs) and is based on the Scope of Work outlined in Section 3.0 of this Facilities Study Report.</p>

<p>Transmission Engineering</p> <p>Department</p>	<p>Prepared by: <u>G A Theriault, P.Eng.</u></p> <p>Approved by: <u>T G Leopold, P.Eng.</u></p>	<p>Customer Operations checked by: _____</p> <p>Division approved by: _____</p>
--	---	--