



**Interconnection Feasibility Study Report  
GIP-084-FEAS-R2**

**System Interconnection Request #84  
50 MW Wind Generating Facility  
Pictou County (L-7004)**

August 17, 2007

Control Centre Operations  
Nova Scotia Power Inc.

## Executive Summary

The Interconnection Customer submitted an Interconnection Request to NSPI for a proposed 50 MW wind generation facility interconnected to the NSPI 230kV transmission line L-7004 between 67N-Onslow EHV and 3C-Port Hastings, approximately 32 km from 67N-Onslow EHV near Salt Springs, Pictou County.

No significant concerns regarding short-circuit level, voltage flicker, or voltage control were found, provided that the project design meets NSPI requirements for low-voltage ride-through, reactive power range and voltage control system.

Excessive thermal loading on L-6503 at the 50N-Trenton terminal was found under single contingency conditions, and therefore the circuit breaker and associated switches and current transformers at the Trenton end of this circuit must be updated from 1200A to 2000A.

There is sufficient transmission capacity to accommodate this project with all transmission elements in service. However, loss of L-8003 between 79N-Hopewell and 67N-Onslow EHV during times of high flow across the Onslow Import interface may result in the section of L-7004 between the POI and Onslow to exceed its summer thermal rating, and production from the IR#84 generation facility may be curtailed.

It is assumed that the Interconnection Customer's facility substation is located at the Point of Interconnection, and therefore the non-binding cost estimate excludes any 230kV spur line that might be required.

Because the Point of Interconnection at L-7004 is considered a Bulk Power System (BPS) element, it must be designed and constructed in accordance with the NPCC Bulk Power System Protection Criteria, and the terminals of L-7004 at 67N-Onslow and 3C-Port Hastings must be updated to BPS compliance.

The direct cost of interconnection, assuming that this is the only project in the vicinity to proceed, is estimated to be \$9,790,000.

Because this project can impact transmission congestion between Cape Breton and Onslow, there is the potential requirement for significant transmission reinforcement, depending on the amount of generation that is added in the vicinity. The requirement for such reinforcements will be determined in a subsequent System Impact Study.

## Table of Contents

	Page
Executive Summary .....	ii
1 Introduction .....	1
2 Scope .....	1
3 Assumptions .....	2
4 Projects with Higher Queue Positions .....	3
5 Objective .....	4
6 Short-Circuit Duty .....	4
7 Voltage Flicker .....	5
8 Thermal Limits.....	5
9 Voltage Control .....	6
10 System Security.....	6
11 Expected Facilities Required for Interconnection.....	7
12 NSPI Interconnection Facilities Cost Estimate.....	9
13 Issues to be addressed in SIS.....	9
13.1 Steady-state post-contingency analysis .....	10
13.2 System stability for the following faults.....	10

## 1 Introduction

The Interconnection Customer submitted an Interconnection Request to NSPI for a proposed 50 MW wind generation facility interconnected to the NSPI 230kV transmission line L-7004 between 67N-Onslow EHV and 3C-Port Hastings, approximately 32 km from 67N-Onslow EHV near Salt Springs. The Interconnection Request is for Energy Resource Interconnection Service (ERIS). The Interconnection Customer signed a Feasibility Study Agreement to study the connection of their proposed generation to the NSPI transmission system. This report is the result of that Study Agreement.

This project is listed as Interconnection Request #84 in the NSPI Interconnection Request Queue, and will be referred to as IR #84 throughout this report.

## 2 Scope

The Interconnection Feasibility Study (FEAS) report shall provide the following information:

- i. Preliminary identification of any circuit breaker short circuit capability limits exceeded as a result of the interconnection;
- ii. Preliminary identification of any thermal overload or voltage limit violations resulting from the interconnection;
- iii. Preliminary description and non-bonding estimated cost of facilities required to interconnect the Generating Facility to the Transmission System, the time to construct such facilities, and to address the identified short circuit and power flow issues.

Subsequent to this FEAS, a System Impact Study (SIS) will examine the project in more detail in the context of Interconnection Requests ahead of this IR #84. This may include system stability issues, single contingencies and extreme contingencies, off-nominal frequency operation, low voltage ride-through, harmonic current and voltage distortion, system protection, Special Protection System interaction, Automatic Generation Control action, and islanded operation. The impacts on neighboring power systems and the requirements set by reliability authorities such as the North American Electric Reliability Council (NERC) and the Northeast Power Coordinating Council (NPCC) will be addressed in the SIS, including the Bulk Power System status of IR #84 in accordance with the NPCC A-10 Criteria<sup>1</sup>. The SIS may identify requirements and system upgrades that are not identified in the FEAS.

---

<sup>1</sup> NPCC Document A-10, *Classification of Bulk Power System Elements*, 2007 04 28.

### 3 Assumptions

The Point of Interconnection (POI) and configuration studied is as follows:

- i. A 50 MW wind farm with unspecified wind turbines. For the purposes of this study, it is assumed that the generators are asynchronous induction generators with external reactive support (Static Var Compensation). If other machines are used, the results of this analysis may require revision.
- ii. The generation technology used must meet NSPI requirement for reactive power capability of 0.95 capacitive to 0.95 inductive at the high voltage terminals of the Interconnection Facilities. It is also required to provide high-speed Automatic Voltage Regulation to maintain constant voltage at the high voltage terminals of the Interconnection Facilities.
- iii. The Interconnection Customer indicated a 230kV interconnection point to accommodate the potential for expansion in the future. It should be noted, however, that this FEAS is limited to the current application for interconnection of 50 MW and makes no comment on the feasibility of future expansion. This point on L-7004 is approximately 32 km from 67N-Onslow EHV substation, within the section between Onslow and Trenton that was originally designed and operated at 138kV.
- iv. The wind generating facility is assumed to be located in close proximity to the POI on L-7004 and therefore the Interconnection Facility is also the wind farm substation. If the wind farm substation is located remote from the POI, then a separate 230kV transmission line connecting the wind farm substation to the POI switching station is required, with a separate Facility substation including circuit breaker.
- v. No information was provided regarding the transformer; therefore it is assumed that there will be one 230kV transformer with a base rating of 40 MVA and a top rating of 55 MVA. Transformer impedance is assumed to be 7% (on 40 MVA ONAN base) and 5 fixed taps between -5% and +5%. Collector voltage will be at the discretion of the Interconnection Customer. It should be noted that NSPI standard distribution voltage is 25kV.

This FEAS is based on the assumption that projects that are ahead of this project in the Generation Interconnection Request Queue will not proceed, however the potential impact of those projects will be reviewed qualitatively.

## 4 Projects with Higher Queue Positions

As of 2007 06 18 the following projects have a higher Queue Position than IR #84, and have the status indicated.

### **In Service and committed generation projects**

Wind Generation – 30.5 MW – connected to L-5027 (in-service)

Wind Generation – 14.0 MW – connected to L-5573 (in-service)

Wind Generation – 20.0 MW – distribution connected (in-service)

Wind Generation – 40.0 MW – distribution connected (committed)

### **Generation projects with a higher Queue position, not yet committed**

IR 008 Wind – Guysborough, L-5527B, 15 MW – FAC Complete

IR 017 Wind – Lunenburg, L-6004, 100MW – SIS in Progress

IR 023 Wind – Inverness, L-6549, 100MW – SIS in Progress

IR 042 Wind – Cape Breton, New 138kV line, 100MW – SIS in Progress

IR 044 Wind – Colchester, L-6503, 35MW – FEAS in Progress

IR 045 Wind – Cumberland, L-6535, 35MW – SIS Complete

IR 046 Wind – Colchester, L-6513, 32MW – FEAS in Progress

IR 056 Wind – Cumberland, L-5058, 60MW – FEAS in Progress

IR 067 Wind – Annapolis, L-5026, 40MW – FEAS in Progress

IR 068 Wind – Digby, L-5533, 35MW – FEAS in Progress

IR 072 Wind – Guysborough, L-6515, 100MW – FEAS in Progress

IR 079 Wind – Antigonish, L-6515, 50MW – FEAS in Progress

IR 080 Wind – Cumberland, L-5550, 30MW – FEAS in Progress

IR 081 Wind – Shelburne, L-5027, 50MW – FEAS in Progress

IR 082 Wind – Colchester, L-5040, 45MW – FEAS in Progress

IR 083 Wind – Shelburne, L-6021, 150MW – FEAS in Progress

This IR #84 and IR #8, IR #23, IR #42, IR #44, IR #72, and IR #79 affect the interface known as Onslow Import. Onslow Import is presently a congested interface from time to time. If any of the projects IR #8, IR #23, IR #42 IR #44, IR #72 or IR #79 proceed, the results of this FEAS must be updated to reflect the impact of increased Onslow Import flow on IR #84, and any transmission upgrades that might be required for this or other projects ahead in the queue. In addition to the above transmission Interconnection Requests, there are 24.5 MW of distribution connected wind generation proposals ahead of this IR #84 which may have an impact on the results of this FEAS.

## 5 Objective

The objective of this FEAS is to determine the primary physical requirements to interconnect 50 MW of generation at the designated location. The assessment will identify potential impacts on the loading of transmission elements, which must remain within their thermal limits. Any potential violations of voltage criteria will be identified and addressed. If the proposed new generation increases the short-circuit duty of any circuit breakers beyond their rated capacity, the circuit breakers must be updated. Single contingency criteria are applied for the Energy Resource Interconnection Service assessment.

This FEAS does not produce a binding estimate of all costs and changes that may be required to interconnect the facility. These costs are limited to facility additions/changes that are in the immediate vicinity of the proposed generating facility and any other system costs that are foreseen at the time this report is completed.

This assessment does not include any determination of facility changes/additions required to increase system transfer capabilities that may be required to the Bulk Power System to meet the design and operating criteria established by the Northeast Power Coordinating Council (NPCC) and/or the North American Reliability Corporation (NERC) or required to maintain system stability. These requirements will be determined by the subsequent interconnection System Impact Study (SIS).

## 6 Short-Circuit Duty

The maximum (future) expected short-circuit level on 230kV systems is 10,000 MVA. The short-circuit levels in the area before and after this development are provided in Table 6-1 below.

<b>Table 6-1: Short-Circuit Levels. Three-phase MVA<sup>2</sup></b>		
<b>Location</b>	<b>This project in service</b>	<b>This project not in service</b>
<b>All transmission facilities in service</b>		
67N-Onslow EHV B52	3841	3735
3C-Port Hastings	2865	2812
230kV Interconnection Point	1960	1810
<b>Minimum conditions<sup>3</sup></b>		
230kV Interconnection Point	833	685

<sup>2</sup> Classical fault study, flat voltage profile.

<sup>3</sup> L-7004 open between 3C-Hastings and Project #84 POI.

The maximum short-circuit level at the POI is presently 1810 MVA. Although the actual increase in short-circuit levels will be dependent on the specific type of generator installed, the increase will bring the short-circuit level to not more than 1960 MVA at the POI. Under contingency operation, with the generator at Point Tupper off-line and wind farm only connected to 3C-Port Hastings (L-7004 open at 67N-Onslow), the short-circuit level will be approximately 685 MVA at the POI.

The interrupting capability of 230kV circuit breakers at 67N-Onslow EHV and 3C-Port Hastings is at least 10,000 MVA which will not be exceeded by this development.

### **7 Voltage Flicker**

Because the minimum Short Circuit Ratio at the POI is 13.5 (based on proposed plant rating of 50 MW), and the generator is assumed to be based on induction generator technology, therefore voltage flicker is not a concern for this project.

### **8 Thermal Limits**

The section of line L-7004 between Route 289 and 67N-Onslow (including the POI) is constructed with 556 kcm Dove ACSR conductor designed for maximum operating temperature of 60°C. The conductor has a thermal rating of 233 MVA summer and 307 MVA winter. The section of L-7004 between Route 289 and 3C-Port Hastings is constructed with 795 kcm Drake ACSR conductor with a higher ampacity (294 MVA summer and 387 MVA winter). Since power flows from east to west in this part of the Nova Scotia power system (from Cape Breton towards Onslow and Brushy Hill), the only concern for this IR#84 is the rating of the Dove conductor between the POI and 67N-Onslow. There is sufficient transmission capacity to accommodate this project with all transmission elements in service.

Loss of L-8003 can also result in high flows on L-6503 between 50N-Trenton and 1N-Onslow. Switchgear and associated equipment at 50N-Trenton (50N-607) must be upgraded to 1500 amps.

The single contingency loss of the double-circuit tower at the Strait of Canso results in the tripping of L-8004 and L-7005. With IR #84 operating at rated load, and east-west transfers below the level were existing Special Protection Systems



(SPS)<sup>4</sup> operate, this contingency causes the Onslow end of L-7004 to exceed its summer rating by 15%. This is within the Long Term Emergency rating of the line, which assumes that the System Operator can relieve the loading through manual re-dispatch, such as curtailing the output of IR #84.

## **9 Voltage Control**

This project, like all new generating facilities must be capable of providing both lagging and leading power factor of 0.95, measured at the 230kV terminals of the Interconnection Facility substation, at all production levels up to the full rated load of 50 MW. A centralized controller will be required which continuously adjusts individual generator reactive power output within the plant capability limits and regulates the voltage at the 230kV bus voltage. The voltage controls must be responsive to voltage deviations at the 230kV terminals of the Interconnection Facility substation, be equipped with a voltage set-point control, and also have facility that will slowly adjust the set-point over several (5-10) minutes to maintain reactive power just within the individual generators capabilities. Details of the specific control features, control strategy and settings will be reviewed and addressed in the SIS.

The NSPI System Operator must have manual and remote control of the voltage set-point and the reactive set-point of this facility to coordinate reactive power dispatch requirements.

This facility must have low-voltage ride-through capability in accordance with FERC Order 661a<sup>5</sup>. The SIS will examine the generator/plant capabilities and controls in detail specify any options, controls and additional facilities that are required to achieve low-voltage ride-through.

## **10 System Security**

The NSPI transmission system has limited east to west transfer capability. Transmission corridors between Sydney and Halifax are often operated to security limits. This project increases flow across the Onslow Import interface. Generation rejection Special Protection Systems<sup>6</sup> (SPS's) are utilized to increase system stability limits to maximize east to west power transfers. Depending on the impact

---

<sup>4</sup> Also known as Remedial Action Schemes, SPS's are defined by NPCC as "A protection system designed to detect abnormal system conditions, and take corrective action other than the isolation of faulted elements." *NPCC Document A7 - Glossary of Terms*.

<sup>5</sup> Post-transition Period LVRT Standard; "Interconnection for Wind Energy", Federal Energy Regulatory Commission, Docket RM05-4-001; Order No. 661-A December 12, 2005.

<sup>6</sup> Also known as Remedial Action Schemes, SPS's are defined by NPCC as "A protection system designed to detect abnormal system conditions, and take corrective action other than the isolation of faulted elements." *NPCC Document A7 - Glossary of Terms*.

of other generation additions ahead of IR #84 in the IR queue, significant transmission system upgrades may be required to integrate IR#84.

This generating facility will also increase loading on the Onslow South corridor (Truro to Halifax) by replacing generation south and west of Truro. This may require increased reactive support requirements in the Halifax area or invoke facility additions that can reduce the reactive support requirements. This will be evaluated in the SIS.

The SIS will determine the facility changes that are required to permit higher transmission loadings while maintaining compliance with NERC/NPCC standards and in keeping with good utility practices.

## 11 Expected Facilities Required for Interconnection

We expect the following facilities will be required assuming that the projects ahead of IR #84 in the Interconnection Request queue, do not proceed.

### Additions/Changes to NSPI systems

Develop a switching substation at the POI with L-7004 (near Salt Springs) consisting of:

- i. Three 230kV circuit breakers and associated switches in a ring-bus arrangement,
- ii. Control building and protection systems,
- iii. Control and communications between the POI switching station and NSPI SCADA system,
- iv. Structures to turn L-7004 into new switching station.
- v. Any conductors needed to connect the wind farm to the POI will use 556 Dove ACSR conductor rated 100°C conductor temperature.
- vi. Control and Communications between the POI and NSPI SCADA system (to be specified)
- vii. Because the POI at L-7004 is considered a Bulk Power System (BPS) element, it must be designed and constructed in accordance with the NPCC Bulk Power System Protection Criteria<sup>7</sup>, and the terminals at 67N-Onslow and 3C-Port Hastings must be updated to BPS compliance.

---

<sup>7</sup> NPCC Document A-5: *Bulk Power System Protection Criteria*

**Requirements for the Interconnection Customer’s Interconnection Facility**

- i. Assuming the Interconnection Customer substation is in close proximity to the POI, a separate substation may not be needed.
- ii. Facilities to provide 0.95 leading and lagging power factor when delivering rated output (50 MW) all at the 230kV bus when the voltage at that point is operating between 95 and 105 % of nominal.
- iii. Centralized controls. These will provide centralized voltage set-point controls and reactive power set-point controls acting to control the voltage on the 230kV system and the reactive output of the machines. Responsive (fast-acting) controls are required. The controls will also include a curtailment scheme which will limit or reduce total output from the facility, upon receipt of a telemetered signal from NSPI’s SCADA system. The controller will also limit the load ramp rate of the facility to within limits set by NSPI and/or telemetered from NSPI’s SCADA system.
- iv. NSPI to have control and monitoring of reactive output of this facility, via the centralized controller. This will permit the NSPI Operator to raise or lower the voltage set-point and change the status of any reactive power controls remotely. NSPI will also have remote manual control of the load curtailment scheme.
- v. Low voltage ride-through capability in accordance with FERC Order 661a.
- vi. Real-time monitoring (RTU’s) of the interconnection substation and facilities for NSPI to execute high speed rejection of generation (transfer trip) if determined by SIS.
- vii. Accessible and tree-cleared lands or Rights Of Way (ROW) acceptable to NSPI Interconnection Facilities for design and construction of any required new transmission line or Transmission Provider's substation.
- viii. Environmental approval for the lands or right-of-ways (if required).

## 12 NSPI Interconnection Facilities Cost Estimate

Table 12-1: Cost Estimates		
	Determined Cost Items	Estimate
i	Uprate L-6503 switchgear at 50N-Trenton	\$200,000
ii	Develop 230kV substation (Salt Springs)	\$1,500,000
iii	Develop 230kV ring bus with three circuit breakers	\$6,000,000
iv	Protection, control, communication	\$500,000
v	Uprate L-7004 terminals to BPS	\$700,000
vi	Contingency (10%)	\$890,000
	<b>Total of Determined Cost Item</b>	<b>\$9,790,000</b>
To be Determined Costs		
vii	System additions to increase east-west transfer capability	TBD (SIS)

NSPI estimates the time required to construct the above facilities at 12-24 months provided that no more than 2 to 3 projects per year go forward, and assuming all easements and permits are provided and complete.

## 13 Issues to be addressed in SIS

The SIS must determine the facilities required to operate this facility at full capacity, withstand the contingencies as defined by NPCC/NERC and identify any restrictions that must be placed on the system following a first contingency loss. The SIS will be conducted with the assumption that all projects higher-queued will proceed and the facilities associated with those projects are installed.

The assessment will consider but not be limited to the following. The facility additions/changes required to increase NSPI east to west transfers under system normal conditions (all transmission in-service) over the range of NSPI loads and with interruptible loads on or off. Some of the interfaces that may be constrained and should be included in the assessment are as follows.

- i. Cape Breton Export
- ii. Onslow Import
- iii. Onslow South
- iv. Metro reactive reserve requirements
- v. NS – NB export/import

### **13.1 Steady-state post-contingency analysis**

All elements within acceptable voltage and thermal limits under the following single contingencies, in accordance with NPCC<sup>8</sup> and NERC<sup>9</sup> criteria.

- i. L-8004
- ii. Hopewell transformer 79N-T81
- iii. L-8003

### **13.2 System stability for the following faults**

Loss of any element without a fault

- i. L-8004
- ii. Hopewell transformer 79N-T81
- iii. L-8003

Three-phase fault cleared in normal time:

- i. L-8003 at Onslow end
- ii. L-8003 at Hopewell end
- iii. L-8001 at import and export limits

Single-phase to ground fault cleared in backup time (Breaker Failure)

- i. L-8003 at Onslow with failure of 67N-812 (lose L-8002)

Single-phase to ground fault on separated circuits of double-circuit tower:

- i. L-8004 plus L-7005 at Canso Crossing
- ii. L-7003 plus section of L-7004 at Trenton

---

<sup>8</sup> NPCC criteria are set forth in its A-2 Document *Basic Criteria for Design and Operation of Interconnected Power Systems*

<sup>9</sup> NERC transmission criteria are set forth in *NERC Reliability Standards TPL-001, TPL-002, TPL-003*

Any changes to SPS schemes required for operation of this generating facility, in addition to existing generation and facilities that can proceed before this project, will be determined by the SIS as well as any required additional transmission facilities. The determination will be based on NERC and NPCC criteria as well as NSPI guidelines and good utility practice. The SIS will also determine the contingencies for which this facility must be curtailed.